

**PROJECT
INFO**

Public Notice
County of Gloucester
Reconstruction of Barnsboro Intersection, Main Street (CR 553A), Breakneck Road/Center Street (CR 603) and Richwood Rd (CR 609) Township of Mantua

Reconstruction of Barnsboro Intersection, Main Street (CR 553A), Breakneck Road/Center Street (CR 603) and Richwood Road (CR 609), Township of Mantua

The County of Gloucester will be completing improvements to the Barnsboro Intersection, Main Street (CR 553A), Breakneck Road/Center Street (CR 603) and Richwood Road (CR 609), Township of Mantua.

PROJECT BACKGROUND: The County of Gloucester has contracted South State, Inc. for improvements to the Barnsboro Intersection, Main Street (CR 553A), Breakneck Road/Center Street (CR 603) and Richwood Road (CR 609). The project is being completed in order to address congestion and safety concerns at the intersection.

THE PROJECT: This Project consists of the relocation of the Richwood Road (CR 609) leg of the existing 5 legged intersection to a new unsignalized intersection on Breakneck Road (CR 603). The remaining standard 4 way intersection of Main Street (CR 553A) and Breakneck Road/Center Street (CR 603) will be widened to provide a formal left turn leg on all approaches with a new traffic signal system construction. The signal system will be solar powered to decrease demand on the power grid. Retaining walls will be constructed along the northerly leg of Main Street (CR 553A) as well as along a portion of Breakneck Road (CR 603). The signal will employ a new more efficient timing sequence to alleviate delays. Detention basins will be constructed along the new relocated section of Richwood Road.

Several utility poles will be impacted by the roadway reconstruction which will require aerial lines to be relocated. All utility work will be performed by the respective utility companies.

During construction, traffic will generally be maintained by two way or alternating traffic. Residents shall have access to their driveways at all times. Driveway aprons within the project limits shall be maintained by the contractor during construction.

PROJECT STATUS: The project will begin construction on or about the week of July 11, 2011. This project is anticipated being completed within 150 days after start date.

For Further Information Contact:

County of Gloucester
Office of the County Engineer
1200 North Delsea Drive
Clayton, NJ 08312-1000
Telephone: 856-307-6600
FAX: 856-307-6606

